

Project Controls Expo, Australia – 26<sup>th</sup> November 2019

Melbourne Cricket Ground, Melbourne

## Performance Measurement on a Connected Site

---

**Rhys Craigie**

Alliance Systems Lead, Western Program Alliance

**Phil Hendy**

Innovation and Continuous Improvement Manager,  
Western Program Alliance



WESTERN  
PROGRAM ALLIANCE



# About the Speakers

Rhys Craigie – Alliance Systems Lead

&

Phil Hendy - Innovation and Continuous Improvement Manager

- Currently work for Western Program Alliance as part of the Level Crossing Removal Projects,
- Work side by side to generate the most value from Connected Sites,
- Both are passionate about changing the construction industry



# About the Topic



WESTERN  
PROGRAM ALLIANCE



Project Controls  
EXPO  
Melbourne, Australia

# About the Topic

## Topic outline

In this presentation we'll explain:

- 'What is the Connected Site' and how it started,
- What Connected Site set out to achieve,
- The journey to date and challenges faced,
- What we have created and
- Where we are going next.

# The Lead Up



WESTERN  
PROGRAM ALLIANCE



Project Controls  
EXPO  
Melbourne, Australia


# The Lead Up

Why it all started

Is there anything more to say?

Then the facts:

- Resource shortage
- A saturation of work




# The Lead Up


How it all started

The collaboration of three key elements:


Government (LXRP)



Technology



Construction



# The Lead Up

The mantra of Connected Sites was simple:


*“A solution that was rapidly deployable, cheap and real-time.”*

A solution that was Problem First, not Technology led.




# The Lead Up

From the holistic idea




# The Lead Up

From the holistic idea through to



# The Lead Up

through to the Final Solution



# Aviation Road Pilot



WESTERN  
PROGRAM ALLIANCE



Project Controls  
EXPO  
Melbourne, Australia


# Aviation Road Pilot

What is an 'Reinforced Earth Wall'?

- Structure made of three key elements:
  - Precast Panels (roughly 2x2m and 1.4t each),
  - Fill Material and
  - Metal straps (tying to the precast into the compacted material)
- Relies on the correct sequence of concurrent activities


Why is the 'Reinforced Earth Wall' important?

- Is the Projects critical path activity,
- A delay in that could result in a delay in project completion



# Aviation Road Pilot

The Northern RE Wall Construction at Aviation Road



# Aviation Road Pilot

## With the Critical Path in Mind- A New Focus

What problems did we want to solve?

- How much Fill has been placed today vs Planned?
- How many panels have been installed today vs Planned?

Associated KPI's

- Plant Hours per widget,
- Labour Hours per widget,
- Cost per widget.



# Aviation Road Pilot

## Constraints

- Only 6 weeks left of Pilot
- Infrastructure was just up and running

## How?

- Implementing 'Collaborative Planning'
- Detailed Milestones
- Agreed on Minimal Viable Product



Detailed Planning using a Pull Plan



# Aviation Road Pilot

## What we knew

- Planned vs Actual was the critical measure
- Targets changed frequently

## What we needed to allow for


- Ability to add Daily/Weekly Targets
- All Fill Material types need to be tracked
- A distinction between Direct vs Stockpile placement

Target Entry	Weekly Target Entries
Records	Records
Concrete m3	Concrete m3
Type A Tonnage	Type A Tonnage
General Tonnage	General Tonnage
RE/Wall Tonnage	RE/Wall Tonnage
<input type="button" value="SUBMIT"/> <input type="button" value="CANCEL"/>	<input type="button" value="SUBMIT"/> <input type="button" value="CANCEL"/>
Fill General	Fill General
Fill Type A	Fill Type A
Fill RE/Wall	Fill RE/Wall
Concrete	Concrete
Records	Records

# Aviation Road Pilot

## RE Wall Fill Material Tracking – What we did

- Created an App
- Gave the Gate Keeper the responsibility
- At each entry, details were logged directly to the system
- Demonstrated Real-Time Tracking of Fill



Total Fill Today


73.7 Tonnes



# Aviation Road Pilot

## RE Wall Fill Material Tracking - Did it work?

- Fill Material Tracking was a great success
- Several add-on benefits including the removal of some administrative effort
- Instantly shows if there might be any issues through the visuals.



# Aviation Road Pilot

## RE Wall Panel Tracking – The Theory


- Overlay of Panel GPS Location (from Model),
- Correlate the position of Installation Crane,
- Assume a stationary crane over the alignment represented an install.

3...



Panel Installed


GPS Sensors



# Aviation Road Pilot

## RE Wall Panel Tracking – What we did

- Used existing GPS Sensors
- Increased accuracy and data pack intervals (1 min to 15 sec)
- Placed two sensors on the installation Crane (Body and end of Boom)



# Aviation Road Pilot

## RE Wall Panel Tracking - Did it work?

- No... Why?
- Relied on:
  - GPS sensitivity which had a large scatter, therefore required aggregation, and
  - An algorithm and AI which didn't get to a working solution
- BUT, watch this space!



# Exciting Steps Forward



WESTERN  
PROGRAM ALLIANCE



Project Controls  
EXPO  
Melbourne, Australia

# Exciting Steps Forward

## Connected Sites version 2.0

The pilot was a success and will be utilized on the next Project/s

- Expanding the Existing Use Cases through:
  - Geofencing for cost code reconciliation
  - Utilizing Machine Learning
- Developing new Use Cases, including:
  - Prestart and Toolbox attendances,
  - Gate Keeper Processes and
  - Individual Precast Panel Tracking.






# Exciting Steps Forward

## Prestart and Toolbox attendance


- Removes the paper attendance form,
- Records attendance with a simple scan,
- Uses existing mandatory ID Card,
- Collates meeting content,
- All stored in central location and
- Can be readily reported on.



# Exciting Steps Forward

## Gate Keeper Processes


- Major Workflow removes several paper forms, including:
  - Driver Inductions and
  - Dockets
- Records vehicles currently on site,
- Time In and out of site,
- Actual Deliveries made vs Planned,
- Visibility of locations of where deliveries are placed,
- Plus many more.



# Exciting Steps Forward

## Individual Precast Panel Tracking

- Transforms an entire process through full visibility, by:
  - Including the Supply Chain,
  - Embedding Baseline, Forecast and Actuals for:
    - Cast,
    - Delivery and
    - Installation.
- Associated escalations if Forecast is exceeded and
- Incorporates QA documentation.



# Exciting Steps Forward


Date: 27/08/2019

Phase: Cast  
 Panel ID: RA/07  
 Cast Date: 17/08/2019  
 Delivery Forecast: 25/08/2019  
 Installation Forecast: 29/08/2019

Phase: Delivered  
 Panel ID: RA/05  
 Cast Date: 15/08/2019  
 Delivered Date: 22/08/2019  
 Installation Forecast: 27/08/2019

Phase: **CAST**  
 Panel ID: RA/06  
 Cast Date: 14/08/2019  
 Delivered Date: 21/08/2019  
**Installation Forecast: 26/08/2019**

Phase: Installed  
 Panel ID: RA/09  
 Cast Date: 12/08/2019  
 Delivered Date: 20/08/2019  
 Installed Date: 25/08/2019



Key		Element Cast		Element Delivered		Element Installed		Element Behind Forecast

Thank you



WESTERN  
PROGRAM ALLIANCE



Project Controls  
EXPO  
Melbourne, Australia